

**ARENAC COUNTY DRAIN COMMISSIONER**

**DOBSON DRAIN**

**NOTICE OF LETTING**

**NOTICE OF LETTING**

**DATE:** May 21, 2024  
**TIME:** 10:00 a.m.  
**LOCATION:** Spicer Group, Inc.  
441 S. Main Street  
Standish, MI 48658  
**QUESTIONS:** (989) 529-0756

The Arenac County Drain Commissioner will meet on the above date, time and location to receive construction bids for the Dobson Drain. Bids will then be opened and publicly announced.

The Dobson Drain will be let in 2 sections as follows, having the length, average depth and width as shown on plans and/or described below:

*Dobson Drain is an existing open channel drain that is approximately 2 miles in length and contains open channel cleanout, drain restoration, and crossing replacements. Section 1 having an approximate length of 10,700 ft, average depth of 6 ft. and width of 4 ft. Section 2 having an approximate length of 300 ft, average depth of 6ft. and width of 4 ft. This Notice of Letting, the plans, specifications, and bid proposal shall be considered a part of the contract. The following items will be required and a contract let for same:*

**DIVISION I: STA. 0+00 to STA. 10+00 & STA. 13+00 to STA. 110+09**

**OPEN CHANNEL CONSTRUCTION**

1,303	Lin. Ft.	Drain Restoration
8,537	Lin. Ft.	Channel Cleanout
6,640	Lin. Ft.	Spoil Leveling (One Side)
3,200	Lin. Ft.	Spoil Hauling
1	Lump Sum	Site Clearing

**CROSSINGS**

**No. 1 - Sta. 3+89 - Concrete Drive, John J. Little**

45	Lin. Ft.	87" Span x 63" Rise C.M.P.A.(Aluminized)
40	Sq. Yd.	Miscellaneous Plain Riprap

**No. 2 - Sta. 4+71 - Concrete Drive, R. & C. Nowacki**

1	Lump Sum	Cleanout Existing Crossing
---	----------	----------------------------

**No. 2A - Sta. 6+35 - Footbridge, Grier, J**

1	Lump Sum	Cleanout Existing Crossing
---	----------	----------------------------

**No. 3 - Sta. 7+04 - Forest Street, City of Standish**

1	Lump Sum	Cleanout Existing Crossing
---	----------	----------------------------

**No. 4 - Sta. 8+60 - Mill Street, City of Standish**

1	Lump Sum	Cleanout Existing Crossing
---	----------	----------------------------

**No. 6 - Sta. 14+15 - Railroad, Lake State Railway**

1	Lump Sum	Cleanout Existing Crossing
---	----------	----------------------------

No. 7 - Sta. 16+36 - Private Crossing, Sequin Thomas E. Jr & Denise

1 Lump Sum Remove Existing Crossing

No. 8 - Sta. 17+92 - Front Street, City of Standish

1 Lump Sum Cleanout Existing Crossing

No. 9 - Sta. 20+64 - Beaver Street, City of Standish

1 Lump Sum Cleanout Existing Crossing

No. 10 - Sta. 25+58 - Court Street, City of Standish

1 Lump Sum Cleanout Existing Crossing

No. 11 - Sta. 27+55 - Cedar Street (M-61), Michigan Department of Transportation

1 Lump Sum Cleanout Existing Crossing

No. 12 - Sta. 38+34 - Air Park Drive, City of Standish

74 Lin. Ft. 87" x 63" C.M.P.A. (Aluminized)

40 Sq. Yd. Miscellaneous Plain Riprap

No. 13 - Sta. 40+71 - Private Foot Bridge, Mersadies Adult Care LLC

1 Lump Sum Cleanout Existing Crossing

No. 14 - Sta. 61+37 - Air Park Drive, City of Standish

100 Lin. Ft. 81" x 59" C.M.P.A. (Aluminized)

30 Sq. Yd. Miscellaneous Plain Riprap

No. 15 - Sta. 66+86 - Driveway Crossing, Arenac County Road Commission

1 Lump Sum No Work

No. 16 - Sta. 87+31 -Johnsfield Rd, Arenac County Road Commission

50 Lin. Ft. 73" x 55" C.M.P.A. (Aluminized)

30 Sq. Yd. Miscellaneous Plain Riprap

No. 17 - Sta. 108+41 -Deep River Road, Arenac County Road Commission

70 Lin. Ft. 48" C.M.P.

20 Sq. Yd. Miscellaneous Plain Riprap

**SOIL EROSION AND SEDIMENT CONTROL**

550 Sq. Yd. Miscellaneous Plain Riprap

50 Lin. Ft. Grass Spillway

150 Lin. Ft. Riprap Spillway

1,000 Lin. Ft. Riprap Toe of Slope Protection

350 Sq. Yd. Riprap Bank Protection

8 Each 10" and Larger Tile Outlet

10 Each 6" to 8" Tile Outlet

4 Each 4" to and Smaller Tile Outlet

35 Each Plain Riprap Splash Pad

**MAINTENANCE ACCESS CULVERTS**

9 Each 15" Surface Outlet Tube - 40'

2 Each 18" Surface Outlet Tube - 40'

1 Each 24" Surface Outlet Tube - 40'

1 Each 36" Surface Outlet Tube - 40'

**MISCELLANEOUS ITEMS**

1 Lump Sum Traffic Control

1 Each Lower Ex. 8" Watermain

2 Each Lower Ex. 10" Watermain

2 Each Water Service Lead

1 Each Remove and Abandon Ex. San. Structure

1	Lump Sum	Seeding, Fertilizing, and Mulching
1	Lump Sum	Cleanup and Restoration
1	Lump Sum	Hydro-Seeding

**DIVISION II: STA. 10+00 to STA 13+00**

**OPEN CHANNEL CONSTRUCTION**

133	Lin. Ft.	Channel Cleanout
133	Lin. Ft.	Spoil Hauling
1	Lump Sum	Site Clearing

**No. 5 - Sta. 11+16 - Main Street (US-23), Michigan Department of Transportation**

167	Lin. Ft.	12' Span x 8' Rise Concrete Box Culvert
1	Lump Sum	Precast Concrete Headwalls and Wingwalls
150	Lin. Ft.	Curb and Gutter, Removal
545	Sq. Yd.	Pavement, Removal
415	Lin. Ft.	4" Perforated Tile with Sock
116	Sq. Yd.	Sidewalk, Removal
32	Cu. Yd.	Embankment, CIP
431	Cu. Yd.	Excavation, Earth
205	Cu. Yd.	Subbase, CIP
60	Sq. Yd.	MDOT 21AA Aggregate Base, 5 inch
610	Sq. Yd.	MDOT 21AA Aggregate Base, 8 inch
120	Cu. Yd.	Sub-Grade Undercutting
9	Ton	Hand Patching
409	Ton	MDOT HMA, 4EML
69	Ton	MDOT HMA, 5EML
180	Lin. Ft.	Curb and Gutter, Conc, MDOT Det F6
90	Lin. Ft.	Curb, Conc, Det E1
1053	Sq. Ft.	Sidewalk, Conc, 4 inch
4	Each	4' Dia. MH/CB
36	Lin. Ft.	12" R.C.P. C-76-IV Storm Sewer
17	Lin. Ft.	18" R.C.P. C-76-IV Storm Sewer
57	Lin. Ft.	Remove Existing Storm Sewer
1	Lump Sum	Connect Existing 10" Tile to Proposed Manhole
1	Lump Sum	Pavement Marking
1	Lump Sum	Traffic Control

**No. 5a - Sta. 11+16 - Alexander R - HMA Parking Lot**

320	Sq. Yd.	Pavement, Removal (Parking Lot)
320	Sq. Yd.	MDOT 21AA Aggregate Base, 8 inch

**WATER MAIN LOWERING**

2	Each	Cut and Cap Ex 8" Water Main
65	Lin. Ft.	8" DI Water Main
1	Each	Connect to Ex 8" Water Main w/ Tapping Tee and Valve
1	Each	Connect to Ex 8" Water Main w/ Cut in Tee
1	Each	1" Copper Water Service Reconnection
1	Lump Sum	Water Main Testing

**MISCELLANEOUS ITEMS**

1	Lump Sum	Site Clearing
1	Lump Sum	Dewatering and Water Control

1	Lump Sum	Shoring System
1	Lump Sum	Seeding, Fertilizing, and Mulching
1	Lump Sum	Cleanup and Restoration
6	Each	Storm Drain Inlet Protection
535	Sq. Yd.	Riprap Bank Protection
20	Days	Inspection Days (Minimum)

This Notice of Letting, the plans, specifications and bid proposal shall be considered a part of the Contract. The Contract will be let in accordance with the Contract Documents now on file at the Arenac County Drain Commissioner's Office and available to interested parties. Bidding Documents, including plans and specifications, may be examined at the following locations beginning **Tuesday, April 23, 2024**:

**Spicer Group Inc.: Digital documents available on website [www.spicergroup.com](http://www.spicergroup.com), with a \$22.00 charge to download**

A security deposit drawn payable to the **Dobson Drain Drainage District** in the form of a cashier's check, money order, certified check or bidders bond shall be submitted with any bids. No cash will be permitted. The security deposits of all unsuccessful bidders shall be returned after the Contract is awarded.

A **mandatory pre-bid conference** will be held at **10:00 a.m.** on the **2nd day of May, 2024**, at the office of **Spicer Group, Inc., 441 S. Main Street, Standish, Michigan 48658**. It is a requirement that any prospective General Contractor bidding attend this meeting. Representatives of the Drainage District and Spicer Group, Inc. will be present to discuss the project. Attendance is required for sealed bids to be accepted. Spicer Group, Inc. will transmit to all prospective bidders of record an Addendum as Spicer Group, Inc. considers necessary in response to questions arising at the conference. Oral statements may not be relied upon and will not be legally effective.

The Contract will be awarded to the lowest responsive and responsible bidder for each Division giving adequate security for the performance of the work and meeting all conditions represented in the Instructions to Bidders. The Contract completion date and the terms of payment will be announced at the time and place of letting. If no satisfactory bids are received, we reserve the right to reject any and all bids and to adjourn to a time and location as we shall announce.

The following is a condensed description of the land constituting the Dobson Drain Drainage District. The description of the area that is served by the Dobson Drain consists of lands situated in Sections 2-3, and 9-11 of City of Standish, T.18N.-R.04E., Arenac County, Michigan, Sections 9 and 10 of Lincoln Township, T.18N.-R.04E., Arenac County, Michigan.

**City of Standish, T.18 N. R.04 E., Arenac County, Michigan.**

In Section 2— The Southwest ¼ of the Southeast ¼ and the Southwest ¼ of the Section.

In Section 3 – The Southeast ¼ of the Southeast ¼ of the Section.

In Section 9 – The Northwest ¼ of the Northeast ¼ and the South ½ of the Northeast ¼ of the Section.

In Section 10 – The North ½ of the Section.

In Section 11 – The Northwest ¼ and the Northeast ¼ of the Northeast ¼ of the Section.

**Lincoln Township, T.18 N. R.04 E., Arenac County, Michigan.**

In Section 9 – The Northeast  $\frac{1}{4}$  of the Northeast  $\frac{1}{4}$  and the Northwest  $\frac{1}{4}$  and the North  $\frac{1}{2}$  of the Southwest  $\frac{1}{4}$  and the Southeast  $\frac{1}{4}$  of the Section.

In Section 10 – The West  $\frac{1}{2}$  of the Southwest  $\frac{1}{4}$  and the Northeast  $\frac{1}{4}$  of the Southwest  $\frac{1}{4}$  and the Northwest  $\frac{1}{4}$  of the Southeast  $\frac{1}{4}$  of the Section.

Dated: 4-23-24

*Larry Davis*

---

Larry Davis  
Arenac County Drain Commissioner